



Todd county

Morrison County

proposed cable locations



230th St 230th St 230th St 230th St 140th St 140th St 140th St 140th St

Existing facility

proposed ped location

20'x20' existing private easement

Placing two cables (900pr and 400pr) and a 1.25" armored innerduct along 140th St, to be crossing Morrison Line Road from the East, @ approximately 32' south of the 140th Street (230th Street) C/L, from Eastern R/W boundary to existing facilities 38' West from C/L.

Innerduct will be placed to a 6" pedestal, placed @ 35' East of Morrison Line Road C/L. Cable/innerduct will be plowed, except under roadbeds, where it will be directionally bored. @ 60" depth.

Work date: 06/21/2013 - 09/01/2013

Project: E.434276
Engineer: Ben Buchholz
(320) 255-8533



CR 219 10th Ave Morrison Line Rd Morrison Line Rd 10th Ave Morrison